

AD-A087 915

WOODWARD-CLYDE CONSULTANTS PLYMOUTH MEETING PA
NATIONAL DAM INSPECTION PROGRAM. AUBURN DAM (NDS I.D. NUMBER PA--ETC(U)
JUN 80


F/6 13/13

DACW31-80-C-0018

NL

UNCLASSIFIED

1 of 2
AD
A087915



AD A087915

✓ WOODWARD-CLYDE CONSULTANTS
✓ DACW31-80-C-0018

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

② National Dam Inspection Program, Auburn Dam


DELAWARE RIVER BASIN

Schuykill County

AUBURN DAM, SCHUYLKILL COUNTY,
PENNSYLVANIA

(NDS I.D. NO. PA 00670)
(DER I.D. NO. 54-163)

PHASE I INSPECTION REPORT,
NATIONAL DAM INSPECTION PROGRAM



DTIC
LECTER
AUG 14 1980

157
DHON 31-29-C-0018

Prepared by:

WOODWARD-CLYDE CONSULTANTS
5120 Butler Pike
Plymouth Meeting, Pennsylvania 19462

Submitted to:

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

JUNE 1980

This document has been approved
for public release and sale; its
distribution is unlimited.

344-157

7/5

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of the Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to expeditiously identify those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, testing and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify the need for more detailed studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected, and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<i>in time</i>
By	<i>50 on file</i>
Distribution/	
Availability Codes	
Dist	Avail and/or special
<i>A</i>	<i>23</i>

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

Name of Dam: Auburn Dam
County Located: Schuylkill County
State Located: Pennsylvania
Stream: Schuylkill River
Coordinates: Latitude 40° 36.5'
Longitude 76° 6.4'
Date of Inspection: May 1, 1980

✓ Auburn Dam is owned by the state of Pennsylvania under the jurisdiction of the Department of Environmental Resources, Office of Resource Management. The dam, built under Pennsylvania Act 441, entitled "Schuylkill River Act", was completed in October 1950. Visual inspection of the exposed sections of the dam and review of the limited available data and simplified calculations presented in Appendices D and G indicate that Auburn Dam is in good condition. It is noted that the entire spillway and apron were submerged and could not be inspected. Therefore, a complete visual assessment of the structure could not be performed.

In accordance with criteria established by Federal (OCE) Guidelines, the recommended spillway design flood for this "Intermediate" size dam and "High" hazard potential classification is the Probable Maximum Flood (PMF).

Calculations presented in Appendix D indicate that the structure will pass about 89 percent of the PMF without overtopping the embankment. Therefore, the spillway system for this structure is considered to be "Inadequate" but not "Seriously Inadequate".

It is recommended that the following items of routine maintenance and surveillance be undertaken as soon as practical.

- (1) The remaining trees and brush on the left earth embankment section should be removed.
- (2) Damaged pilasters should be repaired to prevent loss of support to the hand railing on the top of the dam.

AUBURN DAM, NDS I.D. No. PA 00670

- (3) Surficial joint deterioration of the right non-overflow section should be periodically inspected. If deterioration of these zones becomes excessive, they should be cleaned and patched.
- (4) Seepage through the right non-overflow section should also be periodically monitored and evaluated. Repairs to deteriorated joints caused by seepage would include sealing of the structure/joint from the upstream side of the dam.

An operation and maintenance manual for small dams has been prepared by the Department of Environmental Resources, Division of Completed Projects, Bureau of Operations. Portions of the manual apply to this structure. It is important that persons concerned with the structure are familiar with the procedures contained in the manual. Since there are no formal warning procedures for this structure, one should be developed to warn downstream residents of impending high flows.

Mary F. Beck
Mary F. Beck, P.E.
Pennsylvania Registration 27447E
Woodward-Clyde Consultants

7/2/80
Date


John H. Frederick, Jr.
John H. Frederick, Jr., P.E.
Maryland Registration 7301
Woodward-Clyde Consultants

7/1/80
Date

APPROVED BY:

Henry Beck

31 July 1980
Date



OVERVIEW
AUBURN DAM, SCHUYLKILL COUNTY, PENNSYLVANIA

TABLE OF CONTENTS

	<u>PAGE</u>
Preface	i
Assessment and Recommendations	ii
Overview Photograph	iv
 SECTION 1 - PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	4
 SECTION 2 - ENGINEERING DATA	
2.1 Design	6
2.2 Construction	6
2.3 Operational Data	6
2.4 Evaluation	6
 SECTION 3 - VISUAL INSPECTION	
3.1 Findings	7
3.2 Evaluation	9
 SECTION 4 - OPERATIONAL PROCEDURES	
4.1 Procedures	10
4.2 Maintenance of the Dam	10
4.3 Maintenance of Operating Facilities	10
4.4 Warning Systems In Effect	10
4.5 Evaluation	10
 SECTION 5 - HYDROLOGY/HYDRAULICS	
5.1 Evaluation of Features	11
 SECTION 6 - STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	14
 SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1 Dam Assessment	16
7.2 Remedial Measures	16
 APPENDIX	
A Visual Inspection	
B Engineering Data, Design, Construction and Operation	
C Photographs	
D Hydrology/Hydraulics	
E Plates	
F Geology	
G Stability Analysis	

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
AUBURN DAM
NATIONAL ID NO. PA 00670
DER NO. 54-163

SECTION 1
PROJECT INFORMATION

1.1 General.

a. Authority. The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

b. Purpose. The purpose of the inspection is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Auburn Dam was constructed across the Schuylkill River to form a desilting basin as part of the Schuylkill River Project, Pennsylvania Act 441. It is a concrete gravity structure consisting of a central 500 foot long ogee spillway section, non-overflow concrete sections at each end of the spillway, and a 120 foot earth embankment beyond the left non-overflow section. The overall length of the dam is about 820 feet.

The ogee gravity spillway, crest elevation 473, has a maximum design base width of about 61 feet and a maximum design height from the foundation to the crest of the non-overflow section of 58 feet. The maximum design height of the spillway crest above the downstream apron elevation is 39 feet, and the maximum design height of the non-overflow crest above the downstream apron is 51 feet. The bucket at the downstream toe of the spillway has a radius of 14 feet and a thickness of five feet, extending about 14.6 feet downstream from the projected toe of the ogee weir. The downstream apron design elevation is seven feet above the foundation elevation. As-built drawings or dimensions are not available to determine the actual heights or base width of the gravity sections, which are dependent on the foundation conditions encountered during construction. The "Final Report of the Schuylkill Project Engineers on Schuylkill River, Pennsylvania, 1947-

1951" states: "The maximum height of the dam is 46 feet of which about 28 feet are below the original river bed." Assuming the top of culm (Plate 2, Appendix E) as original river bed, the foundation elevation would be 426. Taking "height of dam" to mean spillway crest, the foundation elevation would be 427.

The dam foundation design included grouting with holes extending 25 feet below the foundation in a single line on five foot centers at the heel of the spillway and non-overflow sections. The cement grouting was apparently to be done after the gravity structure was constructed.

The gravity non-overflow sections at each end of the spillway have a width of eight feet for the top nine feet, plus concrete curbs which add an additional two feet of width near the top. Below the eight foot wide section, the downstream base batters at 6.5 on 10, and the upstream base has a batter of 1 on 20. The right non-overflow section has been backfilled with rock spoil and the left non-overflow section has been backfilled with zoned materials protected by derrick stone; see Plates 3 and 4, Appendix E.

Beyond the left non-overflow section is an earth embankment which ties the non-overflow section to natural ground. The earth embankment has a top width of about 30 feet. The upstream, central and core trench portions of the embankment are constructed of impervious fill, and the downstream portion is constructed of pervious fill. Both upstream and downstream slopes are 3H:1V and are protected by rock spoil. The core trench is 10 feet wide at the bottom, and both upstream and downstream slopes are 1.25H:1V.

The right non-overflow section is tied to the right abutment by a backfill zone approximately 25 feet in length. Impervious fill was used for the upstream and central portions, and pervious fill for the downstream portion. There is no core trench beneath the backfill. A one foot thick layer of rock spoil protects the slopes and the crest.

b. Location. The dam is located on the Schuylkill River, approximately one mile northwest of Auburn, Pennsylvania, in South Manheim and West Brunswick Townships, Schuylkill County, Pennsylvania. The site is shown on the USGS Quadrangle entitled "Auburn, Pennsylvania" at coordinates N 40° 36.5' W 76° 6.4'. A regional location plan of Auburn Dam is enclosed as Plate 1, Appendix E.

c. Size Classification. The dam is classified as an "Intermediate" size structure by virtue of its estimated 51 foot height and 4,500 acre-foot total storage capacity.

d. Hazard Classification. A "High" hazard classification is assigned consistent with the potential for extensive property damage and possible loss of life along the Schuylkill River downstream of the dam.

e. Ownership. The dam is owned by the Department of Environmental Resources, Office of Resource Management. All correspondence should be sent to Resources Management, Bureau of Operations, Department of Environmental Resources, Post Office Box 1467, Harrisburg, Pennsylvania 17120.

f. Purpose of Dam. The purpose of this dam is to create a desilting basin, originally to trap coal sediment.

g. Design and Construction History. Auburn Dam was constructed as a result of Pennsylvania Act 441, "Schuylkill River Desilting Project", June 1945. Auburn Dam is one of a series of several dams along the Schuylkill River constructed to form desilting basins to trap coal sediment carried by the river.

On September 3, 1947, Sprague & Henwood, Incorporated, was awarded the contract to provide test borings at several sites along the Schuylkill River as part of the Schuylkill River Project. All test borings were completed by February 11, 1948. Justin & Courtney* and Albright & Friel**, both of Philadelphia, Pennsylvania, were the engineers responsible for designing the dams across the Schuylkill River. Auburn Dam was constructed by the Arthur A. Johnson Corporation under Contract No. 35, Pennsylvania GSA No. 100-12. During the early stages of excavation, it was found that a more satisfactory foundation existed 45 feet downstream from the original site as determined from the core borings. The decision was made to move the site of the dam downstream to take advantage of the better foundation conditions. The dam is founded on a "dike of sandstone" approximately 60 feet wide.

The dam was constructed in two stages by the use of cofferdams and diversion channels. The right half of the dam was constructed first with diversion of the river through a temporary diversion channel and construction of an earth dike cofferdam. During the second stage of construction, the river was diverted by means of three 4 x 5 foot conduits through the completed spillway section near the right side. To provide for overflow during high water, the three upper five foot

* Justin & Courtney is now a division of O'Brien & Gere, Syracuse, New York.

** Albright and Friel has since merged with Betz-Converse-Murdoch-Inc., Plymouth Meeting, Pennsylvania.

lifts of one monolith section of the first stage construction were not poured until after the other monoliths were completed. After construction, the three conduits were closed off at the upstream end with concrete stoplogs. The final stoplogs were placed October 26, 1950. The dam was completed on October 31, 1950, for a total cost of \$1,396,939.80.

h. Normal Operating Procedures. All water flows over the weir of the spillway.

1.3 Pertinent Data.

A summary of pertinent data for Auburn Dam is presented as follows.

a.	Drainage Area (square miles)	157
b.	Discharge at Dam Site (cfs)	
	Maximum Known Flood	Unknown
	At Top of Non-overflow Section	82,670
c.	Elevation (feet above MSL)	
	Top of Dam	
	Existing	485.2
	Design	485.0
	Spillway Crest	473.0
	Normal Pool	473+
	Tailwater (5/1/80)	451.0
	Downstream Apron (toe) ⁽¹⁾	434±
	Foundation Elevation ⁽¹⁾	427±
d.	Reservoir (feet)	
	Length at Normal Pool	12,000
	Fetch at Normal Pool (est)	2,500
	Length at Maximum Pool (est)	16,000
e.	Storage (acre-feet)	
	Normal Pool	1,900
	At Top of Non-overflow (est)	4,500
f.	Reservoir Surface (acres)	
	Normal Pool	186
g.	Dam Data	
	Type	Concrete gravity w/ zoned earth embank- ment at left end

(1) Based on discussion contained in Section 1.2, paragraph a.

Length	820 feet
Height (above downstream apron) (1)	51± feet
Crest Width (concrete non-overflow section)	8 feet
Volume	
Concrete	32,000 cubic yards
Earth	10,000 cubic yards
Cutoff	Core trench w/imper- vious backfill be- neath embankment at left end
Grout Curtain	Single line grout curtain at heel of gravity sections
h. Spillway	
Type	Concrete ogee weir
Elevation	473.0 feet
Length	500 feet

(1) See note on previous page.

SECTION 2 ENGINEERING DATA

2.1 Design.

a. Data Available. A summary of engineering data for Auburn Dam is presented in the checklist attached as Appendix B.

b. Design Features. Principal design features are illustrated on the plan, profile and cross-sections of this structure, and are enclosed in Appendix E as Plates 2 through 8. These plates are reproduced from drawings supplied by the Department of Environmental Resources (DER). A description of the design features is presented in Section 1.2, entitled "Description of Project".

2.2 Construction.

A description of the construction history is presented in Section 1.2.

2.3 Operational Data.

There are no operational records maintained. Since all flow passes over the overflow section, there are no minimum flow requirements downstream.

2.4 Evaluation.

a. Availability. All engineering data reproduced in this report and studied for this investigation were provided by the Pennsylvania DER, the Bureau of Dam Safety and the Bureau of Operations.

b. Adequacy. The data included in state files and information received from representatives of the Office of Resource Management were sufficiently adequate to evaluate the design features of the dam, with the exception of the spillway adequacy rating, and no stability analysis was provided.

c. Validity. There is no reason to question the validity of the available data.

SECTION 3 VISUAL INSPECTION

3.1 Findings.

a. General. Observations and comments of the field inspection team are contained in the checklist enclosed herein as Appendix A, and are summarized and evaluated as follows. In general, the ogee section, non-overflow sections and earthen sections of the facilities appear to be in good condition and well maintained. At the time of the inspection, the river was flowing at a normal rate over the spillway, and thus, the ogee section and downstream apron of the spillway could not be inspected.

b. Dam. The vertical alignment of the non-overflow sections and earthen embankment was checked and is presented on sheet 5B of 11, Appendix A. There were no distortions in alignment or grade that would be indicative of either horizontal movement of the monoliths or embankment section or deep seated movement within the foundation.

1. Concrete Non-overflow Sections. The exposed portions of concrete of the non-overflow sections and spray walls were inspected and found to be in good condition. There were no changes in alignment or apparent rotation that would be indicative of foundation movement. Surficial concrete deterioration was limited to the railing pilasters on both left and right non-overflow sections, as shown in Photograph 8, and along some expansion joints on the right spray wall, as shown in Photograph 7. Visible on the outside spray wall surface and downstream gravity section of the right overflow section were leachate deposits, shown in Photographs 4 and 5, indicating a long-term leakage/seepage through the concrete. The leachate deposit shown in Photograph 6 is approximately 18 inches long, nine inches wide and nearly an inch thick.

The bottoms of concrete pilasters supporting railing posts have spalled off, as shown in Photograph 8, and some have been repaired within the last year. Surface cracks of the pilasters and walkway and around the railing posts have been sealed with bituminous material. The long-term existence of these cracks is demonstrated by the buildup of leachate at the bottom of at least one of them, which had water leaking out at the time of the inspection. This water is assessed to be rainwater. These cracks are routinely sealed in an effort to prevent freezing damage in the winter. Railings have recently been painted with aluminum paint.

The backfill around the right non-overflow section and the adjacent embankment, shown in Photograph 3, appears to be in good condition with no significant erosion or sloughing. The fill around the left non-overflow section is protected by derrick stone, shown in Photograph 11, which ranges from four to eight feet thick. It is noted that the interstices of this large stone are not filled with smaller stone. The derrick stone was designed to overlay a two foot thick layer of rock spoil, which in turn overlies a one foot thick layer of gravel bedding. A small amount of erosion was noted at the downstream toe of the left spray wall, shown in Photograph 15, probably resulting from a combination of wave action and foot traffic.

2. Left Embankment Section. There were no distortions in alignment or grade that would be indicative of deep seated movement of the embankment or foundation. The vertical profile is included on sheet 5B of 11, Appendix A. The crest, shown in Photograph 10, is unprotected by vegetation or rock spoil, and is slightly rutted by vehicle tire tracks. Near the junction of the earth embankment crest with the concrete non-overflow section were depressions filled with standing rainwater. Some trees and brush have been removed from the earth embankment adjacent to the non-overflow section, but both upstream and downstream embankment slopes are still covered with trees and light underbrush, as shown in Photograph 13. Rock spoil is visible underwater on the upstream side and is also evident under the forest litter on the upstream and downstream slopes. Minor erosion/settlement/vandalism appears to have occurred above the junction of derrick stone and rock spoil on the downstream slope. The junctions with the abutment are in good condition, both upstream and downstream. The downstream junction of the left embankment with the abutment is shown in Photograph 14. No seepage was noted at the toe of either the embankment section or the backfilled areas of the concrete non-overflow sections.

The dam was formerly lighted at night, and the base of a sawed-off timber utility pole remains in the embankment crest near the concrete left non-overflow section. Earlier this year, the utility pole had been cut off flush with the embankment. Apparently, vandals have tried to remove the electrical cable, and a hole has been dug at the base of the utility pole.

c. Appurtenant Structures.

The exposed portions of the ogee spillway were limited to the spray walls of the structure. Water flowing over the spillway crest was smooth with no indications of cracks or displacements between the monoliths, as shown in Photograph 1.

d. Reservoir. At the time of the inspection, the reservoir was at normal pool, and the slopes to the water's edge were well vegetated and stable. The reservoir is presently being dredged, and it is expected that about 200,000 cubic yards of material will be removed from the pool this summer. It is estimated that the pool capacity is presently reduced by about 20 percent by sediment accumulation.

e. Downstream Channel. The natural channel below the dam is the Schuylkill River, which appears to be in good condition with stable banks and a minimum amount of scour.

3.2 Evaluation.

Inspection of the dam and appurtenant facilities disclosed no evidence of apparent past or present movement that would indicate an existing instability of the dam. Since flow was passing over the spillway at the time of the inspection, the toe of the spillway could not be inspected for undermining, scour or the condition of the apron section. There is no evidence to suggest that the observed seepage through the right non-overflow section is detrimental to structural stability at this time. All exposed structural features of the dam were observed to be in good condition. Trees and brush should be removed from the earth embankment and the slopes restored to their original condition. Although no embankment conditions, apparent erosion or depressions are sufficiently serious to require immediate repair, good practice would indicate repairs on a routine basis. As in the past, damaged pilasters should be repaired to prevent potential loss of support to the hand railing on the top of the dam. The effects of seepage through the right non-overflow section should be periodically monitored and evaluated.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedures.

Operation of the dam does not require a dam tender. All flow discharges directly over the ogee section and downstream into the Schuylkill River.

4.2 Maintenance of the Dam.

The dam is inspected yearly by the Department of Environmental Resources (DER), Bureau of Operations, in Harrisburg. The local Schuylkill River Project office provides routine maintenance of the structure, which includes removal of debris, painting and sealing of any surficial cracks.

4.3 Maintenance of Operating Facilities.

There are no mechanical devices or operating facilities to maintain for this structure.

4.4 Warning Systems In Effect.

According to DER's representative during the time of the inspection, there are no formal warning procedures associated with Auburn Dam.

4.5 Evaluation.

Since there are no operating facilities and since the dam does not require a dam tender, it is judged that the current operating procedure is a satisfactory method of operating the dam. Since a warning procedure does not exist, it is recommended that one be established.

SECTION 5 HYDROLOGY/HYDRAULICS

5.1 Evaluation of Features.

a. Design/Evaluation Data. No original design data were located. Some evaluation data were available in state files, and additional calculations for this investigation are presented in Appendix D.

The large, irregularly shaped watershed is about 14 miles long and ranges from 8 to 18 miles wide, having a total area of 157 square miles. Elevations range from 1,757 in the upper reaches to 473 at the weir elevation. This portion of the Schuylkill River Watershed has higher average rainfall and steeper topography than the lower portions of the river, producing a higher runoff. In the watershed above Auburn Dam are over 20 dams, generally concentrated in the upper portions of the watershed. One of the largest dams is located on Plum Creek about two miles above Auburn reservoir.

The total drainage area is less than 25 percent developed and about 75 percent wooded. Coal lands comprised about 76 square miles of the Schuylkill River Watershed concentrated in the extreme upper reaches. The original sediment problem was created by coal processing methods and, during every rainfall, considerable amounts of silt erode from "culm piles", or mine waste piles. It is not expected that runoff characteristics will change significantly in the near future.

The only information concerning spillway capacity is limited to statements in the "Final Report of the Schuylkill River Engineers on the Schuylkill River, Pennsylvania, 1947 - 1951", and an evaluation located in Department of Environmental Resources (DER) files. The design engineers indicate that the design depth of water on the crest was 12 feet, producing a maximum spillway capacity of 75,000 cfs. A memorandum in DER files indicates that the maximum spillway capacity is 79,000 cfs, based on a weir coefficient of 3.8.

In accordance with criteria established by Federal (OCE) Guidelines, the recommended spillway design flood for this "Intermediate" size dam and "High" hazard classification is the Probable Maximum Flood (PMF).

b. Experience Data. Reservoir levels are not maintained for this dam, and there are no estimates of previous high water levels.

c. Visual Observations. On the date of the inspection, there were no conditions observed that would indicate a reduced spillway capacity during an extreme event. Observations regarding the condition of the downstream channel, spillway and reservoir are located in Appendix A and discussed in greater detail in Section 3.

d. Overtopping Potential. This structure was evaluated by the use of the "HEC-1, Dam Safety Version" computer program. A brief description of the program is included in Appendix D. The presence of upstream dams has been conservatively neglected in computing the inflow hydrograph for Auburn Dam. The dam on Plum Creek has a drainage area of about three square miles and is not a flood control dam. Therefore, it will have a negligible effect on the PMF inflow hydrograph to Auburn Dam. The HEC-1 computed peak PMF inflow is about 93,800 cfs. Calculations for this investigation indicate that the maximum spillway capacity is about 82,670 cfs. Flood routing through the reservoir indicates that the earth embankment portion will be overtopped by about one foot during the full PMF event. Calculations indicate that the spillway is capable of passing about 89 percent of the PMF without overtopping the embankment. The outflow from Auburn Dam was routed downstream to estimate the likelihood that the weir would be submerged during the spillway design storm. A maximum stage of 473 feet at the downstream section during the PMF indicates the maximum spillway capacity would not be appreciably reduced by submergence of the weir.

e. Spillway Adequacy. As the spillway will not pass the full PMF without overtopping the embankment, but passes more than one-half the PMF without overtopping the structure, the spillway is rated as "Inadequate" but not "Seriously Inadequate".

f. Downstream Conditions. About 400 feet downstream of the dam, the Schuylkill River passes under the railroad bridge shown in Photograph 16. About 1.5 miles farther downstream, the Schuylkill River flows under the Route 895 highway bridge at Auburn, Pennsylvania. Auburn itself is built about 40 feet above the Schuylkill River floodplain. Across the river from Auburn is an industrial complex, shown in Photograph 17. Industrial buildings and at least one house at that location would be damaged in the event of a sudden failure of the dam. About eight river miles downstream of Auburn Dam is Port Clinton. Port Clinton is located at the confluence of the Schuylkill River and the Little Schuylkill River, immediately upstream of the point where the two combined rivers flow through a gap in the Blue Mountain Ridge. Portions of Port

Clinton are built within 20 feet above the river bank. The gap in the mountain ridge forms a constriction, possibly causing backwater effects at Port Clinton. Were the dam to fail, particularly not as a result of overtopping during an extreme event, extensive property damage and loss of life would occur, justifying a "High" hazard potential rating.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability.

a. Visual Observations. Visual observations detected no evidence of existing or impending instability of the structure. All exposed items of the structure were inspected and found to be in good condition, except for deteriorated railing pilasters, minor surficial concrete deterioration and construction joint deterioration caused by seepage. However, the entire ogee section was covered with water and could not be thoroughly inspected. There was no distortion along the spillway crest to infer excessive scour downstream, monolith displacement or structural deterioration of the ogee section. Spaces were noted between the derrick stone on the downstream section and the embankment portion, most likely as a result of vandalism, but it is judged that this would not have a significant effect on the stability of the structure in the event it is overtopped.

Construction joint deterioration is occurring within the right non-overflow section and spray wall as evidenced by leachate deposits. There is no evidence detected by visual inspection that the structural integrity of the structure has been affected.

b. Design and Construction Data. No design calculations or as-built drawings were available from which to assess the stability of the overflow and non-overflow sections of the dam. Based on a review of the design drawings, the visual appearance of the structure, and a simplified stability analysis presented in Appendix G, the stability of the dam is judged to be adequate. Although the resultant falls outside the middle third of the base, toe pressures are not considered excessive.

c. Operating Records. There are no operational records for this structure.

d. Post-Construction Changes. Since the completion of the dam in 1950, there have been no modifications made to this structure.

e. Seismic Stability. The dam is located in Seismic Zone 1. Normally it can be considered that if a dam in this zone is stable under static conditions, it can be assumed safe for any expected earthquake conditions. Since the dam is assessed to be stable under static loading conditions at the present time, it can also reasonably be considered to be stable under seismic loading conditions.

SECTION 7 ASSESSMENT/REMEDIAL MEASURES

7.1 Dam Assessment.

a. Evaluation. Visual inspection of the exposed sections of the dam and review of the limited available data indicate that Auburn Dam is in good condition. It is to be noted that the entire spillway and bucket were submerged and could not be inspected. Therefore, a complete visual assessment of the structure could not be performed.

In accordance with criteria established by Federal (OCE) Guidelines, the recommended spillway design flood for this "Intermediate" size dam and "High" hazard potential classification is the Probable Maximum Flood (PMF). Calculations presented in Appendix D indicate the structure will pass about 89 percent of the Probable Maximum Flood without overtopping the embankment. Therefore, the spillway system for this structure is considered to be "Inadequate" but not "Seriously Inadequate".

b. Adequacy of Information. Information available for this investigation, the visual inspection and simplified calculations presented in Appendices D and G were sufficient to indicate that no further investigations are required for this structure beyond monitoring specified below.

c. Urgency. The recommendations presented in the following section should be implemented as soon as practical.

7.2 Remedial Measures.

a. Facilities. It is recommended that the following items of routine maintenance and surveillance be undertaken.

- (1) The remaining trees and brush on the left earth embankment section should be removed.
- (2) Damaged pilasters should be repaired to prevent loss of support to the hand railing on the top of the dam.
- (3) Surficial joint deterioration of the right non-overflow section should be periodically inspected. If deterioration of these zones becomes excessive, they should be cleaned and patched.

- (4) Seepage through the right non-overflow section should also be monitored and evaluated. This work should be performed under the supervision of a registered professional engineer experienced in the design and construction of dams.

b. Operation and Maintenance Procedures. An operation and maintenance manual for small dams has been prepared by the Department of Environmental Resources, Division of Completed Projects, Bureau of Operations. Portions of the manual apply to this structure. It is important that persons concerned with the structure are familiar with the procedures contained in the manual. Since there are no formal warning procedures for this structure, one should be developed to warn downstream residents of impending high flows.

APPENDIX

A

CHECK LIST
VISUAL INSPECTION
PHASE I

Sheet 1 of 11

Name Dam Auburn Dam County Schuylkill State Pennsylvania National ID # PA 00670
Type of Dam Concrete gravity/earth Hazard Category High
Date(s) Inspection 5/1/80 Weather Sunny Temperature 60's

Pool Elevation at Time of Inspection 473.5 M.S.L. Tailwater at Time of Inspection 451.0 M.S.L.

Inspection Personnel:

Mary F. Beck (Hydrologist) Vincent McKeever (Hydrologist)
Arthur H. Duino (Geotechnical/Civil)
Raymond S. Lambert (Geologist)

Mary F. Beck Recorder

Remarks:

Mr. Clifford Romig, Bureau of Operations and Mr. Joseph Bullenger, Schuylkill River Project, were on site and provided assistance to the inspection team.

CONCRETE/MASONRY DAMS

Sheet 2 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
ANY NOTICEABLE SEEPAGE	<i>Slight seepage observed through concrete joint in right non-overflow section. No seepage was observed at toe.</i>	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	<i>Good condition.</i>	
DRAINS	<i>None</i>	
WATER PASSAGES	<i>None</i>	
FOUNDATION	<i>Could not be inspected.</i>	

CONCRETE/MASONRY DAMS

Sheet 3 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Water observed through cracks on right non-overflow section, a long-term condition as evidenced by leachate deposits.	
STRUCTURAL CRACKING	None observed.	
VERTICAL AND HORIZONTAL ALIGNMENT	Appeared good, see Sheet 5B of 11.	
MASONRY JOINTS	Exposed joints in good condition.	
CONSTRUCTION JOINTS	Exposed joints in good condition with some minor deterioration of concrete on downstream side of right non-overflow section..	

EMBANKMENT


Sheet 4 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
SURFACE CRACKS	None observed.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES		Apparent erosion of downstream embankment above the contact with derrick stone.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST		See Sheet 5B of 11.
RIPRAP FAILURES		None observed.

EMBANKMENT


Sheet 5 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
VEGETATION		<i>Upstream and downstream slopes are covered with trees and light underbrush. The crest is unprotected and has vehicle tracks.</i>
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM		<i>Good condition.</i>
ANY NOTICEABLE SEEPAGE		<i>None observed.</i>
STAFF GAGE AND RECORDER		<i>None, remnants of staff gage visible on upstream side of left non-overflow section.</i>
DRAINS		<i>None</i>



FIELD OBSERVATION PLAN
AUBURN DAM

SHEET 5A OF 11



SCALE IN FEET



LOOKING UPSTREAM

OUTLET WORKS

Sheet 6 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	None	
INTAKE STRUCTURE	None	
OUTLET STRUCTURE	None	
OUTLET CHANNEL	None	
EMERGENCY GATE	None. Three 4 ft. x 5 ft. conduits through spillway are closed at upstream end with concrete stop logs.	

UNIGATED SPILLWAY

Sheet 7 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
------------------------------	---------------------	-----------------------------------

CONCRETE WEIR		
---------------	--	--

	<i>Flow over weir appeared uniform. Spillway could not be inspected.</i>	
--	--	--

APPROACH CHANNEL		
------------------	--	--

	<i>N/A</i>	
--	------------	--

DISCHARGE CHANNEL		
-------------------	--	--

	<i>Stable, but the channel at the base of the spillway could not be inspected for erosion or undercutting.</i>	
--	--	--

BRIDGE AND PIERS		
------------------	--	--

	<i>None</i>	
--	-------------	--

GATED SPILLWAY

Sheet 8 of 11

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
CONCRETE STILL	N/A	
APPROACH CHANNEL	N/A	
DISCHARGE CHANNEL	N/A	
BRIDGE AND PIERS	N/A	
GATES AND OPERATION EQUIPMENT	N/A	

INSTRUMENTATION

Sheet 9 of 11

REMARKS OR RECOMMENDATIONS

VISUAL EXAMINATION

OBSERVATIONS

MONUMENTATION/SURVEYS

None

OBSERVATION WELLS

None

WEIRS

None

PIEZOMETERS

None

OTHER

None

RESERVOIR

<u>VISUAL EXAMINATION OF</u>	<u>OBSERVATIONS</u>	<u>REMARKS OR RECOMMENDATIONS</u>
------------------------------	---------------------	-----------------------------------

SLOPES

Reservoir side slopes are moderate to steep and vegetated to waters edge with trees or grass. Debris was noted along reservoir edge.

SEDIMENTATION

At the extreme upstream end of the reservoir sediment has formed bars in the river. It is estimated sediment has reduced normal capacity by 20 percent. The reservoir is being dredged.

DOWNSTREAM CHANNEL

Sheet 11 of 11

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	<i>Schuylkill River forms the downstream channel and appears in good condition below the dam.</i>	

SLOPES

The valley gradient below the dam is approximately 0.001.

APPROXIMATE NO. OF HOMES AND POPULATION

Failure of the dam is likely to wash out the railroad bridge 400 feet downstream of the dam and the Rt. 895 highway bridge 1.7 miles downstream of the dam. Immediately upstream of Rt. 895 is an industrial complex with many employees. Downstream of Rt. 895 is at least one house which would be damaged in the event of failure.

APPENDIX

B

NAME OF DAM Auburn Dam
 ID # PA 00670

CHECK LIST
 ENGINEERING DATA
 DESIGN, CONSTRUCTION, OPERATION
 PHASE I

Sheet 1 of 4

REMARKS

None available.

REGIONAL VICINITY MAP

Plate 1, Appendix E.

CONSTRUCTION HISTORY

See text, Section 1.2

TYPICAL SECTIONS OF DAM

See Appendix E.

OUTLETS - PLAN

DETAILS

Appendix E.

CONSTRAINTS

DISCHARGE RATINGS

- See Appendix D

RAINFALL/RESERVOIR RECORDS

None

ITEM	REMARKS
DESIGN REPORTS	<i>None available.</i>
GEOLOGY REPORTS	<i>See Appendix F.</i>
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	<i>None available.</i>
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	<i>Boring records only</i>
POST-CONSTRUCTION SURVEYS OF DAM	<i>None</i>
BORROW SOURCES	<i>A borrow source is designated on the design drawings, located approximately 1,000 feet northwest of the dam.</i>

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	None
HIGH POOL RECORDS	None
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	See Sheet 4 of 4 under Miscellaneous.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	None, inspection records maintained by Bureau of Operations.


ITEM	REMARKS
SPILLWAY PLANS	
SECTIONS	See Appendix E.
DETAILS	
OPERATING EQUIPMENT PLANS & DETAILS	None
MISCELLANEOUS	<ol style="list-style-type: none"> 1. "Final Report of Schuylkill River Project Engineers on Schuylkill River, PA 1947-1951," provided by Local Schuylkill River Project Office. 2. File maintained by Bureau of Operations was available for review. 3. "Operation and Maintenance Manual for Small Dams", prepared by Bureau of Operations was supplied. 4. The following were supplied by Dept. of Environmental Resources, Bureau of Dam Safety and Waterways Management. 5. A 14 sheet set of design drawings. 6. DER inspection reports. 7. Memorandum describing design features of dam. 8. Copies of inspection report files by local Schuylkill Project Engineers Office.

APPENDIX

C

PHOTOGRAPH LOCATION PLAN
AUBURN DAM

PLATE C-1






DISCHARGE IS UNIFORM OVER
SPILLWAY CREST.

PHOTOGRAPH NO. 1



UPSTREAM SIDE, RIGHT NON-OVERFLOW
SECTION.



ABUTMENT AND TOP OF NON-
OVERFLOW SECTION, RIGHT
SIDE.

PHOTOGRAPH NO. 3



SPRAY WALL, RIGHT SIDE.

PHOTOGRAPH NO. 4




LEACHATE DEPOSITS ON DOWNSTREAM
SIDE OF RIGHT NON-OVERFLOW
SECTION.

PHOTOGRAPH NO. 5



CLOSE-UP OF LEACHATE
DEPOSIT WHICH IS ABOUT
ONE INCH THICK.

PHOTOGRAPH NO. 6



JOINT DETERIORATION ON INSIDE OF
RIGHT SPRAY WALL.

PHOTOGRAPH NO. 7




DETERIORATED PILASTER, UPSTREAM
SIDE OF RIGHT NON-OVERFLOW
SECTION.

PHOTOGRAPH NO. 8



UPSTREAM SIDE, LEFT NON-OVERFLOW
SECTION

PHOTOGRAPH NO. 9



EMBANKMENT CREST AND TOP OF
LEFT NON-OVERFLOW SECTION.

PHOTOGRAPH NO. 10




DOWNSTREAM DERRICK STONE, LEFT
SIDE.

PHOTOGRAPH NO. 11



CONTACT BETWEEN DERRICK STONE
AND EMBANKMENT.

PHOTOGRAPH NO. 12



UPSTREAM SIDE OF EMBANKMENT SECTION.

PHOTOGRAPH NO. 13



DOWNSTREAM JUNCTION OF
EMBANKMENT AND LEFT
ABUTMENT.

PHOTOGRAPH NO. 14



MINOR EROSION AT DOWNSTREAM TOE OF
LEFT SPARY WALL.



DOWNSTREAM RAILROAD BRIDGE.

PHOTOGRAPH NO. 16



DOWNSTREAM DAMAGE CENTER AT
INDUSTRIAL COMPLEX NEAR AUBURN,
PENNSYLVANIA.

APPENDIX

D

AUBURN DAM
CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Large, rolling, 25% developed, coal mining
in upper reaches.
ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 473.0 feet (1900 Acre-Feet).
ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 485.0 feet (4500 Acre-Feet).
ELEVATION MAXIMUM DESIGN POOL: ----
ELEVATION TOP DAM: 485 feet.

SPILLWAY

- a. Elevation 473.0 feet.
b. Type Concrete ogee weir.
c. Width 500 feet.
d. Length ---
e. Location Spillover Central portion of structure.
f. Number and Type of Gates None

OUTLET WORKS:

- a. Type Non-functional construction diversion conduits with
concrete stop logs.
b. Location _____
c. Entrance inverts 448.0 feet.
d. Exit inverts 448.0 feet
e. Emergency draindown facilities None

HYDROMETEOROLOGICAL GAGES:

- a. Type Two reporting National Weather Service Stations within
the watershed.
b. Location _____
c. Records National Weather Service.

MAXIMUM NON-DAMAGING DISCHARGE: Not determined.

ACBURN DAM
HYDROLOGIC AND HYDRAULIC
BASE DATA

Sheet 2 of 11

DRAINAGE AREA: (1) 167 square miles.

PROBABLE MAXIMUM PRECIPITATION (PMP)
FOR 10 SQ. MILES IN 24 HOURS: (2) 23.0 inches.

ADJUSTMENT FACTORS FOR DRAINAGE AREA (%): (3)

Zone	<u>8</u>
6 Hours	<u>88</u>
12 Hours	<u>93</u>
24 Hours	<u>108</u>
48 Hours	<u>117</u>

SNYDER HYDROGRAPH PARAMETERS: (4)

Zone	<u>8</u>
C_p, C_t	<u>1.40, 1.88</u>
L (5)	<u>27 miles</u>
L_{ca} (6)	<u>10 miles</u>
$tp = C_t (L \cdot L_{ca})^{0.3}$	<u>7.88</u>

SPILLWAY CAPACITY AT MAXIMUM
WATER LEVEL (7)

8000 cfs

-
- (1) Measured from USGS maps, 1:250,000 scale.
 - (2) Hydrometeorological Report No. 33, Figure 1.
 - (3) Hydrometeorological Report No. 33, Figure 2.
 - (4) Information received from Corps of Engineers, Baltimore District.
 - (5) Length of longest water course from outlet to basin divide, measured from USGS maps.
 - (6) Length of water course from outlet to point opposite the centroid of drainage area, (see Plate 1, Appendix E) measured from USGS maps.
 - (7) See Sheet 11 of this Appendix.

HEC-1, REVISED
FLOOD HYDROGRAPH PACKAGE

The original "Flood Hydrograph Package" (HEC-1), developed by the Hydrologic Engineering Center, Corps of Engineers, has been modified for use under the National Dam Inspection Program. The "Flood Hydrograph Package (HEC-1), Dam Safety Version", hereinafter referred to as, HEC-1, Rev., has been modified to require less detailed input and to include a dam breach analysis. The required input is obtained from the field inspection of a dam, any available design/evaluation data, relatively simple hydraulic calculations, or information from the USGS Quadrangle maps. The input format is flexible in order to reflect any unique characteristics of an individual dam.

HEC-1, Rev. computes a reservoir inflow hydrograph based on individual watershed characteristics such as: area, percentage of impervious surface area, watershed shape, and hydrograph characteristics determined from regional correlation studies by the Corps of Engineers, Baltimore District. The inflow is routed through the reservoir using spillway discharge data obtained from the field inspection or design data. Flood storage capacity is determined from USGS maps or design information and verified by the field inspection. In the event a spillway cannot discharge 0.5 PMF without overtopping and failure of the dam, downstream channel characteristics obtained from the field inspection and USGS maps are inputted and flows are routed downstream to the damage center and a dam breach analysis is performed.

Included in this Appendix are the HEC-1, Rev. pertinent input values and a summary print-out tables.

BY MFG DATE 5/23/80 SUBJECT _____ SHEET 4 OF 11
CHKD. BY AHD DATE 5/30/80 Auburn Dam JOB No. _____
Hydrology / Hydraulics

Classification (Ref: Recommended Guidelines for
Safety Inspection of Dams)

1. The hazard potential is rated as "High" as there would be loss of life in the event of sudden failure of the dam.
2. The size classification is "Intermediate" based on its 51 ft. height and 4500 Ac-ft storage capacity.
3. The spillway design flood, based on size and hazard classification, is the Probable Maximum Flood (PMF).

Hydrology and Hydraulic Analysis

1. Design/Evaluation Data. No original design data was available. The "Final Report of Schuylkill River Engineers" lists the spillway capacity as 75,000 cfs with a design head of 12 ft. In 1951 the State estimated the spillway capacity as 79,000 cfs with a weir coefficient of 3.8.

2. Evaluation of Structure

Rainfall and Snyder's hydrograph parameters are shown on sheet 2. The presence of upstream dams has been conservatively neglected.

Elevation - Storage Data, shown on sheet 8

normal pool	473	186 Ac	- design value
	480	215 Ac	} measured from USGS map
	500	370 Ac	

Elevation - Discharge Data, shown on sheet 8

Shape of weir conforms to H_o (design head) = 12 ft.
(Ref. Design of Small Dams, USBR, 2nd ed., p. 378)

F (height of weir) = 10 ft. a minimum value
from design drawing

$$P/H_o = 10/12 = 0.833$$

$$C = 3.87$$

BY MEB DATE 5/23/80

SUBJECT

SHEET 5 OF 11CHKD. BY AHD DATE 5/30/80Auburn Dam

JOB No

Hydrology / Hydraulics

W.S.	H	H/H ₀	C/C ₀	C	L	Q	
473	0					0	
474	1	0.08	0.81	3.13	500	1567	✓
475	2	0.17	0.84	3.25		4597	✓
476	3	0.25	0.86	3.33		8647	✓
478	5	0.42	0.90	3.48		19,470	✓
480	7	0.58	0.93	3.60		33,328	✓
483	10	0.83	0.98	3.79		59,966	✓
485	12	1.00	1.00	3.87		80,436	✓
486	13	1.08	1.0	3.91		91,604	✓
491	18	1.50	1.06	4.10		156,637	✓

The above assumes the weir is not submerged at high flows. Spillway flows are routed down stream (thru a cross section taken from USGS map) to estimate the likelihood of weir submergence.

3. Spillway Adequacy

As the spillway discharges more than 0.5 PMF but less than 1.0 PMF without overtopping the embankment, the spillway is rated as "Inadequate" but not "Seriously Inadequate".

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

RUN DATE* 80/05/17.
 TIME* 07.04.39.

AUBURN DAM
 MAY ID NO. PA 00670 DER NO. 54-163
 OVERTOPPING ANALYSIS

JOB SPECIFICATION									
NO	MHR	MHIN	IDAY	IHR	IMIN	METRC	IPLT	IFRT	NSTAN
300	1	0	0	0	0	0	0	-4	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRTIO= 4 LRTIO= 1
 RTIOS= .50 .80 .90 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
IN	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYDG	IUNG	TAREA	SNAP	IRSDA	IRSPC	RATU	ISNOW	ISAME	LOCAL
1	1	157.00	0.00	157.00	0.00	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	23.00	85.00	93.00	103.00	117.00	0.00	0.00

IRSPC COMPUTED BY THE PROGRAM IS .877

LOSS DATA

LROPT	SIRKR	ULTRK	KTIOL	ERAIN	STKRS	RTIDK	SIRYL	CNSIL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 7.65 CP= .40 NTA= 0

RECESSION DATA

SIRIQ= -1.50 DRCSN= -.05 RTIDR= 2.00

UNIT HYDROGRAPH 81 END-OF-PERIOD ORIGINATES, LAD= 7.69 HOURS, CP= .40 VOL= 1.00										
216.	812.	1664.	2669.	3691.	4539.	5114.	5330.	5153.	4899.	
4488.	4189.	3909.	3649.	3405.	3178.	2966.	2768.	2583.	2411.	
2250.	2100.	1960.	1829.	1707.	1593.	1487.	1388.	1295.	1209.	
1128.	1053.	982.	917.	856.	799.	745.	696.	649.	606.	
565.	528.	493.	460.	429.	400.	374.	349.	325.	304.	
283.	265.	247.	230.	215.	201.	187.	175.	163.	152.	
142.	133.	124.	116.	108.	101.	94.	88.	82.	76.	
71.	66.	62.	58.	54.	50.	47.	44.	41.	38.	
36.										

END-OF-PERIOD FLOW						
MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP 0
0						

SUM 23.61 21.06 2.54 2136057.
(600.)(535.)(65.)(60486.40)

HYDROGRAPH ROUTING

OUTFLOW HYDROGRAPH

ISTAQ	ICOMP	IECUN	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAU10
OUT	1	0	0	0	0	1	0	0
ROUTING DATA								
QLOSS	CLOSS	AVG	IKES	ISAME	IOPT	IPMP	LSIK	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS NSTDL								
1	0	LAG	AMSKK	X	TSK	STORA	ISFRAT	
		0	0.000	0.000	0.000	-473.	-1	

STAGE	473.00	474.00	475.00	476.00	478.00	480.00	483.00	485.00	486.00	491.00
FLOW	0.00	1567.00	4597.00	8647.00	19470.00	33328.00	59966.00	80436.00	91604.00	156637.00

SURFACE AREA= 186. 215. 390.

CAPACITY= 0. 1402. 7366.

ELEVATION= 473. 480. 500.

CREL	SFWID	COQW	EXPW	ELEV	COOL	CAKEA	EXPL
473.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA			
TOPEL	COQU	EXPD	DAMWID
485.2	0.0	0.0	0.

CREST LENGTH 0. 250. 320.
 AT OR BELOW
 ELEVATION 485.2 486.3 490.0

HYDROGRAPH ROUTING

DOWNSTREAM SECTION

QLOSS	CLOSS	ICOMP	IECON	ITAPE	JPLY	JFRT	INAME	ISTAGE	IAUTO
0.0	0.000	1	0	0	0	0	1	0	0
ROUTING DATA									
0.0	0.000	AVG	IRIS	ISANE	IOPT	IPMP		LSIR	
			1	1	0	0		0	
NSTPS NSTDL LAG AMSKK X ISK STORA ISPRAT									
			0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

QIN(1)	QIN(2)	QIN(3)	ELNVT	ELMAX	RLNTH	SEL
.0250	.0250	.0250	445.0	480.0	200.	.00100

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC

STA	ELEV	STA	ELEV
0.00	480.00	450.00	490.00
450.00	460.00	460.00	450.00
460.00	450.00	460.00	700.00

STORAGE	0.00	1.20	2.43	3.69	5.02	6.43	7.92	9.48	11.12	12.96
	15.18	17.79	20.79	24.17	27.95	32.12	36.68	41.62	46.96	52.69
OUTFLOW	0.00	728.53	2308.33	4557.49	7484.04	11028.03	15184.86	19954.40	25339.76	31073.97
	37832.11	45701.75	54790.17	65215.19	77092.17	90532.00	105641.28	122522.68	141275.50	161996.00
STAGE	445.00	446.84	448.68	450.53	452.37	454.21	456.05	457.89	459.74	461.58
	463.42	465.26	467.11	468.95	470.79	472.63	474.47	476.32	478.16	480.00
FLOW	0.00	728.53	2308.33	4557.49	7484.04	11028.03	15184.86	19954.40	25339.76	31073.97
	37832.11	45701.75	54790.17	65215.19	77092.17	90532.00	105641.28	122522.68	141275.50	161996.00

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS			
				RATIO 1	RATIO 2	RATIO 3	RATIO 4
				.50	.80	.90	1.00
HYDROGRAPH AT	IN	157.00	1	46894.	75031.	84410.	93789.
	(406.63)	(1327.90)	(2124.64)	(2390.22)	(2655.80)
ROUTED TO	OUT	157.00	1	46623.	74608.	84042.	93408.
	(406.63)	(1320.21)	(2112.67)	(2379.82)	(2645.03)
ROUTED TO	DS1	157.00	1	46609.	74612.	84044.	93419.
	(406.63)	(1319.82)	(2112.76)	(2379.85)	(2645.33)


SUMMARY OF DAM SAFETY ANALYSIS




RATIO OF PMF	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	MAXIMUM RESERVOIR U.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.50		473.00	473.00	485.20		0.00	1733.	46623.	0.00	47.00	0.00
.80		0.	0.	2624. Flood water		0.00	2430.	74608.	0.00	47.00	0.00
.90		0.	0.	82670. storage only		.12	2656.	84042.	2.00	47.00	0.00
1.00						.92	2863.	93408.	5.00	47.00	0.00

PLAN 1	STATION	DS1
	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT
		TIME HOURS
.50	46609.	465.4
.80	74612.	470.4
.90	84044.	471.7
1.00	93419.	473.0
		47.00
		47.00
		47.00
		47.00

APPENDIX


E













- LEGEND**
- | | |
|----------|---------------------------|
| Coal Cut | Shale |
| Clay | Sandstone |
| Sand | Sandstone - Brown |
| Gravel | Sandstone - Shale |
| Boulders | Sandstone - Shale - Brown |
| Shale | |

- SYMBOLS**
- GW = Ground Water
- ◆ = Completed Core Run









2. 4/2/102 1/3000 L...







NOTE: - Reiling and Pilasters not shown
See Sheet No. 12 for details




UPSTREAM SECTION



SECTION D-D





SECTION B-B



DOWNSTREAM ELEVATION SECTION A-A

NOTE: - Reiling and Pilasters not shown.
See Sheet No. 10 for details



GENERAL NOTES:

1. Figures in circles indicate item numbers under which payment will be made, thus (4).
2. Figures in squares indicate monetary amounts, thus \$1.
3. N.T.S. Not to scale.

DATE	REVISION


SCHUYLKILL RIVER PROJECT


PROJECT ENGINEERS

FREDERIC B. HARRIS, FREDERICK H. DECHANT ASSOCIATES
DAY AND ZIMMERMANN, INC. ALBRIGHT AND FRIEL, INC.
JUSTIN AND COURTNEY

AUBURN DESILTING BASIN NO. 1 RIGHT
RIGHT ABUTMENT OF DAM

DATE 3 DEC 1948	COMMONWEALTH OF PENNSYLVANIA JAMES H. DUFF - GOVERNOR DEPARTMENT OF FORESTS AND WATERS M. F. DRAHEL - SECRETARY HARRISBURG, PENNSYLVANIA	CONTRACT NUMBER 35 SHEET NUMBER 8
--------------------	--	--






DETAIL OF SPILLWAY OUTLINE
Scale 1/4" = 1'-0"


Dimension	Distance	Elevation
a	1'-11"	417
b	2'-11"	418
c	1'-11"	419
d	2'-0"	420
e	2'-0"	421
f	1'-11"	422
g	1'-11"	423
h	1'-11"	424
i	1'-0"	425
j	1'-0"	426
k	1'-0"	427
l	1'-0"	428
m	1'-11"	429

Width of Base	Elevation
61'-11"	417.0
60'-6"	418.0
59'-10"	419.0
59'-8"	420.0
58'-7"	421.0
57'-11"	422.0
57'-4"	423.0
56'-8"	424.0


Note: Tables A and B indicate possible elevations and dimensions. True elevations and dimensions to be determined by actual field requirements.




DETAIL OF SPILLWAY
Scale 1/4" = 1'-0"




SPILLWAY CONSTRUCTION DETAILS
Scale 1/4" = 1'-0"




SPILLWAY CONSTRUCTION DETAILS
Scale 1/4" = 1'-0"




SECTION OF SPILLWAY THROUGH CONDUIT
Scale 1/4" = 1'-0"



SECTION OF SPILLWAY THROUGH CONDUIT
Scale 1/4" = 1'-0"




DETAIL OF SPILLWAY OUTLINE
Scale 8 in = 1 ft



DETAIL OF COPPER WATER STOP AND JOINT FILLER
Scale 1/2 in = 1 ft



Indicate
all
work
to be
done
in
this
area




GENERAL NOTES:-


- Figures in circles indicate the item number under which payment will be made.
- Figures in squares indicate manolith numbers thus [1].
- All exposed corners of concrete shall be chamfered 1/2 inch except on curbing.
- All reinforcing bars shall be deformed. All bends shall be made around an 8" diameter pin. Lap all bars 40 diameters unless otherwise noted.
- The clear distance of bars from face of concrete shall be 4 inches unless otherwise noted.
- Reinforcing steel will be paid for at the contract price item No 17.

DATE	REVISION




SCHUYLKILL RIVER PROJECT	
PROJECT ENGINEERS FREDERIC R. HARRIS - FREDERICK H. DECHAMPE ASSOCIATES DAY AND ZIMMERMANN INC. ALBRIGHT AND FRIEL INC. JUSTIN AND COURTNEY	
AUBURN DESILTING BASIN NO. 1 RIGHT OVERFLOW SECTION OF DAM	
DATE 31 DEC 1948	CONTRACT NO. 35
SCALE 1" = 1'-0"	SHEET NUMBER 8
COMMONWEALTH OF PENNSYLVANIA JAMES H. DUFF - GOVERNOR DEPARTMENT OF FORESTS AND WATERS N. F. DRAEMEL - SECRETARY HARRISBURG, PENNSYLVANIA	






Station	Left	Right
1+00	47.71	52.28
1+10	47.71	52.28
1+20	47.71	52.28
1+30	47.71	52.28
1+40	47.71	52.28
1+50	47.71	52.28
1+60	47.71	52.28
1+70	47.71	52.28
1+80	47.71	52.28
1+90	47.71	52.28
2+00	47.71	52.28
2+10	47.71	52.28
2+20	47.71	52.28
2+30	47.71	52.28
2+40	47.71	52.28
2+50	47.71	52.28
2+60	47.71	52.28
2+70	47.71	52.28
2+80	47.71	52.28
2+90	47.71	52.28
3+00	47.71	52.28



- GENERAL NOTES:**
1. All dimensions are in feet and inches.
 2. All dimensions are to the center of the structure.
 3. All dimensions are to the face of the structure.
 4. All dimensions are to the back of the structure.
 5. All dimensions are to the top of the structure.
 6. All dimensions are to the bottom of the structure.
 7. All dimensions are to the side of the structure.
 8. All dimensions are to the front of the structure.
 9. All dimensions are to the rear of the structure.
 10. All dimensions are to the left of the structure.
 11. All dimensions are to the right of the structure.
 12. All dimensions are to the north of the structure.
 13. All dimensions are to the south of the structure.
 14. All dimensions are to the east of the structure.
 15. All dimensions are to the west of the structure.




DATE	REVISION


SCHUYLKILL RIVER PROJECT

PROJECT ENGINEERS
 FREDERIC B. HARRIS - FREDERICK H. DECHANT ASSOCIATES
 DAY AND ZIMMERMAN, INC. ALBRIGHT AND FRIEL, INC.
 JUSTIN AND COURTNEY


AUBURN DESILTING BASIN NO. 1 RIGHT
NON-OVERFLOW SECTION OF DAM

DATE DEC 1948	COMMONWEALTH OF PENNSYLVANIA JAMES H. DUFF - GOVERNOR DEPARTMENT OF FORESTS AND WATERS H. F. DRAEMEL - SECRETARY HARRISBURG, PENNSYLVANIA	CONTRACT NO. 3A SHEET NO. 10
------------------	---	---------------------------------------






PLAN OF RIGHT SPRAY WALL




SECTION E-E


ELEVATION OF RIGHT SPRAY WALL



SECTION A-A



SECTION C-C





SECTION D-D

Table Showing Offset Distances from Sta 11+55 to Face of Spray Wall

ELEVATION	OFFSET
481	10'-0"
475	10'-0"
468	9'-11"
463	9'-10"
458	9'-9"
453	9'-5"
446	9'-9"
443	9'-0"
438	8'-0"
433	9'-7"

Table Showing Offsets for Batter of Top of Each Footing

VERT. DISTANCE	BATTER
1	1/4"
2	1/4"
3	1/4"
4	1/4"
5	1/4"
6	1/4"
7	1/4"
8	1/4"
9	1/4"



GENERAL NOTES:-


- 1 Figures in circles indicate the item number under which payment will be made.
- 2 Figures in squares indicate minimum numbers, thus **1**
- 3 All exposed corners of concrete shall be chamfered 1/2 inches except note otherwise.
- 4 All reinforcing bars shall be deformed. Reinforcing shall be made around an 8-0 inch diameter bar and 10-0 diameter unless otherwise indicated.
- 5 The clear distance of bars from face of concrete shall be 4 inches unless otherwise noted.
- 6 Reinforcing steel will be paid for at the contract price, Item No. 1.

Showing Offset Distances from Sta 14+55 to Face of Spry	
STATION	OFFSET
461	10.00
475	10.00
480	9.11
483	9.10
498	9.10
453	9.09
440	7.98
443	7.87
438	9.08
433	9.78

Table Showing Offsets for
Baths of 1" or 4" For Each Foot
VERT. DISTANCE BATHEN

1'	$\frac{1}{16}$
2'	$\frac{1}{8}$
3'	$\frac{3}{16}$
4'	$\frac{1}{4}$
5'	$\frac{5}{16}$
6'	$\frac{3}{8}$
7'	$\frac{7}{16}$
8'	$\frac{1}{2}$
9'	$\frac{9}{16}$

SECTION D.D



DATE	DIVISION

SCHUYLKILL RIVER PROJECT

PROJECT ENGINEERS

FREDERICK R. HARRIS - FREDERICK H. DECHANT, ASSOCIATES
DAY AND ZIMMERMANN, INC. ALBRIGHT AND FRIEL, INC.
JUSTIN AND COURTNEY

AUBURN DESILTING BASIN NO.1 RIGHT
RIGHT SPRAY WALL OF DAM

DATE DEC 1946	COMMONWEALTH OF PENNSYLVANIA JAMES H. DUFF - GOVERNOR DEPARTMENT OF FORESTS AND WATERS M. F. DRAEDEL - SECRETARY HARRISBURG, PENNSYLVANIA	CONTRACT NUMBER 38 SHEET NUMBER 12
------------------	---	---







Table Showing Details for Entry of 100 for 9 for each 10																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Year	1947	1948	1949	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2423	2424	2425	2426	2427	2428	2429	2430	2431	2432	2433	2434	2435	2436	2437	2438	2439	2440	2441	2442	2443	2444	2445	2446	2447	2448	2449	2450	2451	2452	2453	2454	2455	2456	2457	2458	2459	2460	2461	2462	2463	2464	2465	2466	2467	2468	2469	2470	2471	2472	2473	2474	2475	2476	2477	2478	2479	2480	2481	2482	2483	2484	2485	2486	2487	2488	2489	2490	2491	2492	2493	2494	2495	2496	2497	2498	2499	2500	2501	2502	2503	2504	2505	2506	2507	2508	2509	2510	2511	2512	2513	2514	2515	2516	2517	2518	2519	2520	2521	2522	2523	2524	2525	2526	2527	2528	2529	2530	2531	2532	2533	2534	2535	2536	2537	2538	2539	2540	2541	2542	2543	2544	2545	2546	2547	2548	2549	2550	2551	2552	2553	2554	2555	2556	2557	2558	2559	2560	2561	2562	2563	2564	2565	2566	2567	2568	2569	2570	2571	2572	2573	2574	2575	2576	2577	2578	2579	2580	2581	2582	2583	2584	2585	2586	2587	2588	2589	2590	2591	2592	2593	2594	2595	2596	2597	2598	2599	2600	2601	2602	2603	2604	2605	2606	2607	2608	2609	2610	2611	2612	2613	2614	2615	2616	2617	2618	2619	2620	2621	2622	2623	2624	2625	2626	2627	2628	2629	2630	2631	2632	2633	2634	2635	2636	2637	2638	2639	2640	2641	2642	2643	2644	2645	2646	2647	2648	2649	2650	2651	2652	2653	2654	2655	2656	2657	2658	2659	2660	2661	2662	2663	2664	2665	2666	2667	2668	2669	2670	2671	2672	2673	2674	2675	2676	2677	2678	2679	2680	2681	2682	2683	2684	2685	2686	2687	2688	2689	2690	2691	2692	2693	2694	2695	2696	2697	2698	2699	2700	2701	2702	2703	2704	2705	2706	2707	2708	2709	2710	2711	2712	2713	2714	2715	2716	2717	2718	2719	2720	2721	2722	2723	2724	2725	2726	2727	2728	2729	2730	2731	2732	2733	2734	2735	2736	2737	2738	2739	2740	2741	2742	2743	2744	2745	2746	2747	2748	2749	2750	2751	2752	2753	2754	2755	2756	2757	2758	2759	2760	2761	2762	2763	2764	2765	2766	2767	2768	2769	2770	2771	2772	2773	2774	2775	2776	2777	2778	2779	2780	2781	2782	2783	2784	2785	2786	2787	2788	2789	2790	2791	2792	2793	2794	2795	2796	2797	2798	2799	2800	2801	2802	2803	2804	2805	2806	2807	2808	2809	2810	2811	2812	2813	2814	2815	2816	2817	2818	2819	2820	2821	2822	2823	2824	2825	2826	2827	2828	2829	2830	2831	2832	2833	2834	2835	2836	2837	2838	2839	2840	2841	2842	2843	2844	2845	2846	2847	2848	2849	2850	2851	2852	2853	2854	2855	2856	2857	2858	2859	2860	2861	2862	2863	2864	2865	2866	2867	2868	2869	2870	2871	2872	2873	2874	2875	2876	2877	2878	2879	2880	2881	2882	2883	2884	2885	2886	2887	2888	2889	2890	2891	2892	2893	2894	2895	2896	2897	2898	2899	2900	2901	2902	2903	2904	2905	2906	2907	2908	2909	2910	2911	2912	2913	2914	2915	2916	2917	2918	2919	2920	2921	2922	2923	2924	2925	2926	2927	2928	2929	2930	2931	2932	2933	2934	2935	2936	2937	2938	2939	2940	2941	2942	2943	2944	2945	2946	2947	2948	2949	2950	2951	2952	2953	2954	2955	2956	2957	2958	2959	2960	2961	2962	2963	2964	2965	2966	2967	2968	2969	2970	2971	2972	2973	2974	2975	2976	2977	2978	2979	2980	2981	2982	2983	2984	2985	2986	2987	2988	2989	2990	2991	2992	2993	2994	2995	2996	2997	2998	2999	3000
1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1</																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	



APPENDIX

F

SITE GEOLOGY
AUBURN DAM

Auburn Dam is located within the Appalachian Mountain Section of the Valley and Ridge Physiographic Province. As shown on Plate F-1, the dam is constructed upon the Trimmers Rock Sandstone Formation of Upper Devonian age. This area is situated upon the southern limb of a regional north-northeast trending syncline which crosses much of southern Schuylkill County. Bedrock is exposed on both the upstream and downstream sides of the right abutment. This exposure consists of tan-brown fine grained sandstone with siltstone interbeds and red-brown shale. Bedding strikes to the east-northeast, subparallel to the dam axis, and dips downstream approximately 35 degrees to the north. The shale is fissile and slakes, but the sandstone which dips under the right abutment is sound. Information contained in the Schuylkill River Project report of 1951, states that the dam is founded upon a "dike of sandstone" approximately 60 feet wide, which strikes parallel to the dam alignment. Bedrock jointing strikes to the northwest (nearly parallel to the dam axis) and dips nearly vertical. No bedrock exposures were observed at the left abutment area.

AD-A087 915

WOODWARD-CLYDE CONSULTANTS PLYMOUTH MEETING PA F/G 13/13
NATIONAL DAM INSPECTION PROGRAM. AUBURN DAM (NDS I.D. NUMBER PA--ETC(U)
JUN 80 DACW31-80-C-0018

UNCLASSIFIED

2 of 2

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201

201


END

DATE

FILED

9-80

DTIC



APPENDIX

G

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>1</u> of <u>7</u>
	Project: <u>AUBURN DAM</u>	Job No./File No. <u>79C01167-19</u>
System:		Calculator <u>AMD</u> Date <u>5/30/80</u>
Calculation for: <u>STABILITY</u>		Reviewer <u>HFB</u> Date <u>6/3/80</u>

AUBURN DAM - STABILITY ANALYSIS

ASSUMPTIONS:

- UNIT WEIGHT OF CONCRETE = 150 PCF ✓
- UNIT WEIGHT OF WATER = 62.4 PCF ✓
- SUBMERGED WEIGHT OF SILT = 40 PCF ✓
- EARTH PRESSURE COEFFICIENT OF SILT = 0.5 ✓
- COEFFICIENT OF FRICTION OF ROCK = 0.7 ✓
- COMPRESSIVE STRENGTH OF ROCK = 600 KSF ✓
- ALLOWABLE CONCRETE SHEAR STRENGTH = 55 PSI ✓


FOR CONSERVATISM AND SIMPLICITY, NEGLECT UPSTREAM
 BATTER OF OVERTFLOW AND NON-OVERFLOW SECTIONS.

DETERMINE RESISTANCE OF DAM TO OVERTURNING AND
 SLIDING FOR CONDITION OF FULL POOL AND
 FULL SILT LOAD TO TOP OF SPILLWAY. NEGLECT
 TAILWATER

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>2</u> of <u>7</u>
	Project: <u>AUBURN DAM</u>	Job No./File No. <u>79C01167-19</u>
System:		Calculator <u>AMD</u> Date <u>5/30/80</u>
Calculation for: <u>STABILITY</u>		Reviewer <u>MEB</u> Date <u>6/3/80</u>

OVERFLOW SECTION:



$$\begin{aligned}
 W_1 &= (0.150)(10)(46) = 69.0 \text{ KIPS} \\
 W_2 &= \frac{1}{2}(0.150)(33)(46) = 113.8 \text{ KIPS} \\
 V_1 &= (12)(0.0624)(46) = 34.4 \text{ KIPS} \\
 V_2 &= \frac{1}{2}(0.0624)(46)^2 = 66.0 \text{ KIPS} \\
 S &= \frac{1}{2}(0.50)(0.040)(41)^2 = 16.8 \text{ KIPS} \\
 U &= \frac{1}{2}(0.0624)(50)(43) = 77.8 \text{ KIPS}
 \end{aligned}$$

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>3</u> of <u>7</u>
	Project: <u>AUBURN DAM</u>	Job No./File No. <u>79C01167-19</u>
System:		Calculator <u>AMD</u> Date <u>5/30/80</u>
Calculation for: <u>STABILITY</u>		Reviewer <u>MFJ</u> Date <u>6/8/80</u>

REVISED
6/30/80
AMD ✓

$$\begin{aligned}\sum \overrightarrow{M}_{TOE} &= (34.4)(23) + (66.0)\left(\frac{46}{3}\right) + (77.8)\left(\frac{2}{3}\right)(43) + (6.8)(18.67) \\ &= 791.2 + 1012.0 + 2230.3 + 313.6 \\ &= 4347.1 \text{ FT-KIPS } \checkmark\end{aligned}$$

$$\begin{aligned}\sum \overrightarrow{M}_{TOE} &= (69.0)(38) + (113.8)\left(\frac{2}{3}\right)(33) \\ &= 2622.0 + 2503.6 \\ &= 5125.6 \text{ FT-KIPS } \checkmark\end{aligned}$$

$$F.S. \text{ o.T.} = \frac{5125.6}{4347.1} = 1.18 \checkmark \text{ OK FOR EXTREME LOADING AND CONSERVATIVE ASSUMPTIONS}$$

$$\sum M_{TOE} = 5125.6 - 4347.1 = 778.5 \text{ KIPS } \checkmark$$

$$\sum V_{\text{ext}} = W_1 + W_2 - U = 69.0 + 113.8 - 77.8 = 105.0 \text{ K } \checkmark \downarrow$$

$$e = \frac{\sum M}{\sum V_{\text{ext}}} = \frac{778.5}{105.0} = 7.41 \text{ FT } \checkmark \text{ FROM TOE}$$

$$\frac{43}{3} = 14.33 \text{ FT} > 7.41 \text{ FT}$$

∴ RESULTANT IS OUTSIDE OF MIDDLE THIRD ✓

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>4</u> of <u>7</u>
	Project: <u>HUBURN DAM</u>	Job No./File No. <u>79C01167-19</u>
System:	Calculator <u>AHP</u> Date <u>6/30/80</u>	
Calculation for: <u>STABILITY</u>	Reviewer <u>RFB</u> Date <u>6/30/80</u>	

$$\text{TOE PRESSURE} = \frac{2}{3} \cdot \frac{V}{e} = \frac{2}{3} \cdot \frac{105.0}{7.41} = 9.45 \text{ KSF}$$

ALTHOUGH RESULTANT FALLS OUTSIDE OF MIDDLE
THIRD OF BASE, THE TOE PRESSURE IS NOT
EXCESSIVE FOR ROCK.

SHEAR AT ELEV. 432:

$$V_{432} = \frac{1}{2} (0.0624) (53)^2 - \frac{1}{2} (0.0624) (12)^2 = 83.1 \text{ KIPS}$$

$$N_{MAX} = \frac{3}{2} \frac{V}{bL} = \frac{3}{2} \left(\frac{83.1 + 16.8}{1 \times 39.5} \right) = 3.79 \text{ KSF} = 26.4 \text{ PSI} < 55 \text{ PSI OK}$$

SLIDING:

ASSUME ROCK SHEAR STRENGTH IS 7% OF
COMPRESSIVE STRENGTH.

$$F.S. = \frac{\sum V \tan \phi + cA + \sum cD}{V_1 + V_2 + S}$$

$$= \frac{(69.0 + 113.8 - 77.8)(0.7) + (0.07)(600)(43) + (2)(0.07)(600)(5)}{34.4 + 66.0 + 16.8}$$

$$= \frac{73.5 + 180.6 + 42.0}{117.2}$$

$$= 19.6 \text{ OK}$$

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>6</u> of <u>7</u>
	Project: <u>AUBURN DAM</u>	Job No./File No. <u>79C0167-19</u>
System:	Calculator <u>AHD</u> Date <u>5/30/80</u>	
Calculation for: <u>STABILITY</u>	Reviewer <u>HBB</u> Date <u>6/3/80</u>	

REUSFD
6/30/80
AHD

$$\begin{aligned}\sum \bar{M}_{T \rightarrow E} &= \frac{1}{3}(50)(105.0) + \left[\frac{1}{3}(41) + 5\right](16.8) + \frac{2}{3}(40)(72.4) \\ &= 2030.0 + 313.6 + 1930.7 \\ &= 4274.3 \text{ FT-KIPS} \checkmark\end{aligned}$$

$$\begin{aligned}\sum \bar{M}_{T \rightarrow E} &= (69.6)(36) + (117.6)\frac{2}{3}(32) = \\ &= 2505.6 + 2508.8 \\ &= 5014.4 \text{ FT-KIPS} \checkmark\end{aligned}$$

$$F.S.O.T. = \frac{5014.4}{4274.3} = 1.17 \checkmark \text{ OK FOR EXTREME}$$

CONDITIONS AND
CONSERVATIVE ASSUMPTIONS

$$\sum M_{T \rightarrow E} = 5014.4 - 4274.3 = 740.1 \text{ FT-KIPS} \checkmark$$

$$\sum V_{ERT} = W_1 + W_2 - U = 69.6 + 117.6 - 72.4 = 114.8 \text{ KIPS} \downarrow$$

$$e = \frac{\sum M_{T \rightarrow E}}{\sum V_{ERT}} = \frac{740.1}{114.8} = 6.45 \text{ FT FROM T} \rightarrow \text{E} \checkmark$$


$$\frac{L}{3} = \frac{40}{3} = 13.33 \text{ FT} > 6.45 \text{ FT}$$

\therefore RESULTANT IS OUTSIDE OF MIDDLE THIRD

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>5</u> of <u>7</u>
	Project: <u>AUBURN DAM</u>	Job No./File No. <u>79C01167-19</u>
System:		Calculator <u>AMD</u> Date <u>5/30/80</u>
Calculation for: <u>STABILITY</u>		Reviewer <u>MEB</u> Date <u>6/3/80</u>

NON-OVERFLOW SECTION:



$$W_1 = (2.150)(8)(50) = 69.6 \text{ KIPS} \checkmark$$

$$W_2 = \frac{1}{2} (0.150)(49)(32) = 117.6 \text{ KIPS} \checkmark$$

$$V = \frac{1}{2} (0.0624)(50)^2 = 105.0 \text{ KIPS} \checkmark$$

$$S = \frac{1}{2} (0.50)(40)(41) = 16.8 \text{ KIPS} \checkmark$$

$$U = \frac{1}{2} (0.0624)(50)(40) = 72.4 \text{ KIPS} \checkmark$$

DESIGN CALCULATIONS

Woodward-Clyde Consultants Consulting Engineers, Geologists and Environmental Scientists	Owner:	Page <u>7</u> of <u>7</u>
	Project: <u>AUBURN DAM</u>	Job No./File No. <u>79C01167-19</u>
System:		Calculator <u>AND</u> Date <u>6/30/80</u>
Calculation for: <u>STABILITY</u>		Reviewer <u>MFB</u> Date <u>6/30/80</u>

$$T\text{OE PRESSURE} = \frac{2}{3} \cdot \frac{V_{\text{ERT}}}{e} = \frac{2}{3} \cdot \frac{114.8}{6.45} = 11.9 \text{ KSF}$$

ALTHOUGH RESULTANT FALLS OUTSIDE OF MIDDLE THIRD OF BASE, THE TOE PRESSURE IS NOT EXCESSIVE FOR ROCK.

SHEAR AT ELEVATION 432 (IN CONCRETE):

$$V_{432} = \frac{1}{2} (0.0624)(53)^2 = 87.6 \text{ KIPS}$$

$$N_{\text{MAX}} = \frac{3}{2} \cdot \frac{V}{bL} = \frac{3}{2} \cdot \frac{87.6 + 16.8}{1 \times 36.75} = 4.26 \text{ KSF}$$

$$= 29.6 \text{ PSI} < 55 \text{ PSI OK}$$

SLIDING:

ASSUME ROCK SHEAR STRENGTH IS 7% OF COMPRESSIVE STRENGTH

$$F.S. = \frac{\sum V_{\text{ERT}} \tan \phi + cA + 2cD}{V + S}$$

$$= \frac{(69.6 + 117.6 - 77.4)(0.7) + (0.07)(600)(40) + (2)(0.07)(600)(5)}{105.0 + 16.8}$$

$$= \frac{80.36 + 1680 + 420}{121.8}$$

$$= 17.9 \text{ OK}$$

